BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

BBMP/2018-19/OW/WORK_INDENT32476

Developments of roads and drains from 1st cross to 10th cross in Attur Layout and surrounding areas in Ward no.03

SNo	Estimate Quantity	Item Name	Unit	Negotiated Rates quoted by Sri. K Gopi Reddy	
				Rate in figures	Rate in words
1	3874.68	Earthwork in execavation for foundation of structure like culverts, retaining wall etc., as per drawing and technical specification, including setting out, construction of shoring and bracing, dressing of sides and bottom, back filling with approved material, disposal of balance earth as per specification, including cost of labour, HOM etc., complete. In all kinds of soil by manual means.	Cum	309.10	Rupees Three Hundred Nine And Paise Ten Only
2	651.66	Plain cement concrete M 10 mix with crushed stone aggregate 40mm nominal size mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days complete as per specifications,	Cum	4837.92	Rupees Four Thousand Eight Hundred Thirty Seven And Paise Ninety Two Only
3	1183.56	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. With 20mm and sown size granite metal course aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compcted for walls and bottom including centring shuttering cost of material HOM of machinary curing etc., complete execluding cost of steel as per MORTH specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per specification.	Cum	7635.82	Rupees Seven Thousand Six Hundred Thirty Five And Paise Eighty Two Only
4	80.13	Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications for TMT bars Fe 500.	MT	79911.62	Rupees Seventy Nine Thousand Nine Hundred Eleven And Paise Sixty Two Only
5	156.84	Providing and laying in position plain cement concrete of mix 1:2:4 for sub-structure works like culverts, retaining wall, etc., with cement @ 240 kgs, 40mm and sown size granite metal course aggregates at 0.84 cum and fine aggregates at 0.46 cum machine mixed, with necessary scaffolding, form work etc., including cost of labour, HOM curing etc.,	Cum	5322.18	Rupees Five Thousand Three Hundred Twenty Two And Paise Eighteen Only
6	2674.80	Providing and fixing RCC precast cover slab of 100mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	2523.96	Rupees Two Thousand Five Hundred Twenty Three And Paise Ninety Six Only
7	162.00	Providing and fixing RCC precast cover slab of 250mm thick made out of CC 1:2:4 and jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	5851.44	Rupees Five Thousand Eight Hundred Fifty One And Paise Forty Four Only
8		GST @12%			

Gopi Reddy

Executive Engineer
Project Division
Yelahanka Zone

Contractor